



A SECTION A-A — LONGITUDINAL (through WC zone, looking to rear wall)


Scale 1:50 @ A3 · cut 3900 from front face · roof falls 5° away from viewer (rear eave lower)



B SECTION B-B — CROSS SECTION (through male entrance, wash area & urinal bay)

Scale 1:50 @ A3 · cut 5500 from left end face, looking toward central wall · front on left (as end elevation)

KEY PLAN 1:100 (section positions)



LEGEND

brickwork (cut) · concrete (cut) · compacted fill · natural ground · timber (cut) · DPC / ASSUMED value (red) · hidden line / GIVEN (navy) · visible beyond (grey)

CONSTRUCTION NOTES

1. All dimensions in mm. Levels relative to N.G.L ±0; F.S.L +300 (given). Plan dimensions are GIVEN (Fig. 1); all vertical and constructional sizes in RED are ASSUMED engineering baselines - confirm against project spec.
2. ROOF: 0.5 mm galv. IBR sheeting at 5° mono-pitch on 50x76 SA pine purlins @ max 1100 c/c, on 38x152 rafters over every wall line (max 1115 c/c, 2000 max span), on 114x38 wall plates strapped with hoop iron built 6 courses into brickwork. Beam-fill between rafters at all plates.
3. Roof falls front to rear: front plate FFL+2841, rear plate FFL+2400 (rise 441 = 5045 x tan 5°). Rear 125 half-round gutter to r.w. downpipe at rear-left (r.w. point given). Eaves and verge overhang 300; 25x190 fascia/barge; raised fascia band 333 (190+143) over central entrance bay.
4. WALLS: 115 brickwork throughout (given), 14 MPa bricks in class II mortar, brickforce every 4th course; plaster and paint to client's specification. 230 brick foundation walls up to F.S.L.
5. DPC: 375 micron embossed polyethylene under all walls at F.S.L. LINTELS: 150 deep reinforced concrete over all openings, min 230 bearing each side.
6. FLOOR: 100 thick 20 MPa concrete surface bed with A142 mesh on 250 micron DPM on compacted G5 fill (150 layers, 93% Mod AASHTO); steel-float finish laid to falls to floor traps.
7. FOUNDATIONS: 600x230 20 MPa concrete strip footings, u/s -700 below N.G.L, min 200 into firm natural ground; bearing to be confirmed on site.
8. DRAINAGE: Ø110 uPVC @ 1:40 below slab to IC at central wall, thence to septic tank & soak-away (given). Sleeve where pipes pass foundation walls.
9. OPENINGS: entrance doors 900x2100, cubicle doors 700x2100, internal openings 900x2100 (not shown on source - ASSUMED). Air bricks 215x140 at FFL+2100 c/l. WHB rim FFL+850, urinal lip FFL+610.
10. RAMP: 1:12 concrete, 100 thick on compacted fill with 230 toe nib; 40° splay cheek wings (given).

SCALE BAR 1:50 (metres)

0 — 1 — 2 — 3 — 4 — 5 m

LEVELS SCHEDULE (mm above N.G.L)

Element	Level	AFFL	Shown in	Source
Front wall plate (high eave)	+3141	FFL+2841	B-B	ASSUMED
Roof sheet at A-A cut	+3067	FFL+2767	A-A	ASSUMED
Rear wall plate (low eave)	+2700	FFL+2400	B-B	ASSUMED
Door / opening heads	+2400	FFL+2100	B-B	ASSUMED
Finished floor (F.S.L)	+300	0	both	GIVEN
Natural ground (N.G.L)	±0	-300	both	GIVEN
Top / underside of footing	-470 / -700	-	both	ASSUMED


ABLUTION BLOCK — SECTIONS

A-A Longitudinal · B-B Cross section

Project	**Ablution Block (Fig. 1)**	Scale	**1:50**
Drawing	**Sections A-A & B-B**	Sheet	**A3 landscape**
Drawn by	**Karl (student no.)**	Projection	**Third angle**
Date	**01/10/2026**	Units	**mm**
Checked	**—**	Dwg no.	**A2-Q4 / S-01**

Values in red are ASSUMED (no vertical dims on source).
Read with: Plan & Elevations sheet, Front Elevation, Doors & Latrines set-out.

PROJECTION



THIRD ANGLE